









'GREENLEAF REROOT' - TREE ROOT PROTECTION SYSTEM 3D VIEW

SCALE @ A3: (NTS)

NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ENGINEERS & ARCHITECT'S DRAWINGS.FIGURED DIMENSIONS ONLY (NOT SCALING) TO BE USED. WHERE A CONFLICT OF INFORMATION EXISTS OR IF IN ANY DOUBT - `ASK'.
- CONSULTANTS TO BE INFORMED IMMEDIATELY OF ANY DISCREPANCIES BEFORE WORK PROCEEDS.

- 1. DETAILED DESIGN & SPECIFICATION OF BLUE & GREEN ROOF OR PODIUM SYSTEMS BY THE SUPPLIER, SUBJECT TO APPROVAL
- 2. ALL MEMBRANES / SHEETS TO BE UV STABILISED & ROT PROOF.
- 3. A 100Ø mm EMERGENCY PARAPET OVERFLOW PIPE SHOULD BE PROVIDED ON ALL BLUE ROOFS.

MAINTENANCE REQUIREMENTS FOR GREEN ROOFS

REGULAR INSPECTIONS. ANNUALLY AND AFTER SEVERE STORMS. **INSPECT ALL COMPONENTS INCLUDING SOIL SUBSTRATE,** VEGETATION, DRAINS, IRRIGATION SYSTEMS (IF APPLICABLE), MEMBRANES AND ROOF STRUCTURE FOR PROPER OPERATION, INTEGRITY OF WATERPROOFING AND STRUCTURAL STABILITY. INSPECT SOIL SUBSTRATE FOR EVIDENCE OF EROSION CHANNELS AND IDENTIFY ANY SEDIMENT SOURCES. INSPECT DRAIN INLETS TO ENSURE UNRESTRICTED RUNOFF FROM THE DRAINAGE LAYER TO THE CONVEYANCE OR ROOF

DRAIN SYSTEM INSPECT UNDERSIDE OF ROOF FOR EVIDENCE OF LEAKAGE.

REGULAR MAINTENANCE

REMOVE DEBRIS AND LITTER TO PREVENT CLOGGING OF INLET DRAINS AND INTERFERENCE WITH PLANT GROWTH. SIX MONTHLY AND ANNUALLY OR AS REQUIRED DURING ESTABLISHMENT (I.E. YEAR ONE), REPLACE DEAD PLANTS AS REQUIRED. MONTHLY (BUT USUALLY RESPONSIBILITY OF MANUFACTURER)

POST ESTABLISHMENT, REPLACE DEAD PLANTS AS REQUIRED (WHERE > 5% OF COVERAGE). ANNUALLY (IN AUTUMN) REMOVE FALLEN LEAVES AND DEBRIS FROM DECIDUOUS PLANT FOLIAGE. SIX MONTHLY OR AS REQUIRED REMOVE NUISANCE AND INVASIVE VEGETATION, INCLUDING WEEDS SIX MONTHLY OR AS REQUIRED MOW GRASSES, PRUNE SHRUBS AND MANAGE OTHER PLANTING

(IF APPROPRIATE) AS REQUIRED - CLIPPINGS SHOULD BE REMOVED AND NOT ALLOWED TO ACCUMULATE. SIX MONTHLY OR AS REQUIRED

REMEDIAL ACTIONS

IF EROSION CHANNELS ARE EVIDENT, THESE SHOULD BE STABILISED WITH EXTRA SOIL SUBSTRATE SIMILAR TO THE ORIGINAL MATERIAL, AND SOURCES OF EROSION DAMAGE SHOULD BE IDENTIFIED AND CONTROLLED. FREQUENCY AS

IF DRAIN INLET HAS SETTLED, CRACKED OR MOVED, INVESTIGATE AND REPAIR AS APPROPRIATE. FREQUENCY AS REQUIRED.

	1	I		1
PL6	11.03.25	ISSUED FOR PLANNING		AM
PL5	04.12.24	ISSUED FOR PLANNING		DB
PL4	25.02.22	ISSUED FOR PLANNING		MR
PL3	04.02.22	ISSUED FOR PLANNING		MR
PL2	13.10.21	ISSUED FOR PLANNING		MR
PL1	08.10.21	ISSUED FOR PLANNING		MR
P1	27.08.21	ISSUED FOR COMMENT		MR
ISSUE	DATE	DESCRIPTION		BY
Project En	Project Engineer: MH		Project Director: CK	

Project Engineer: MH

PLANNING



Sandwith House, 52-54 Lower Sandwith Street, Dublin 2, Ireland. Tel: (01) 677 3200 Fax: (01) 677 3164

12 Mill Street, London SE1 2AY, United Kingdom Tel: (0044) 084 5413 2722



of Structural ¹Engineers

1 TERENURE LAND LTD.

CARLISLE SITE KIMMAGE, **RESIDENTIAL DEVELOPMENT**

SuDS DETAILS.

CST-BMD-00-ZZ-DR-C-1205 PL 6

TYPICAL GREEN & BLUE ROOF DETAILS.

BM PROJECT No

21.221